

Notice of variation and consolidation with introductory note

The Environmental Permitting (England & Wales) Regulations 2010

Wessex Water Services Limited
Wastewater treatment works at Rode
Rode Hill
Frome
Somerset
BA11 6PS

Variation number

011560/V003

Permit number

011560

Wastewater treatment works at Rode

Permit number 011560

Introductory note

This introductory note does not form a part of the notice.

Under the Environmental Permitting (England & Wales) Regulations 2010 (schedule 5, part 1, paragraph 19) a variation may comprise a consolidated permit reflecting the variations and a notice specifying the variations included in that consolidated permit.

Schedule 1 of the notice specifies the conditions that have been varied and schedule 2 comprises a consolidated permit which reflects the variations being made. Only the variations specified in schedule 1 are subject to a right of appeal.

This variation concerns the implementation of the integrated catchment permitting approach to the regulation of phosphorus in sewage discharges to the Bristol Avon catchment. The aim of the trial is to achieve a target annual phosphorus load reduction in the catchment that will be spread across a number of wastewater treatment works. The variation incorporates an operating technique document that sets out phosphorus reduction requirements at a number of the individual sites and the overall annual load reduction target for the catchment. The reduction will be achieved by a combination of optimising current phosphorus treatment processes and the implementation of phosphorus treatment at some new sites. The improvements will be funded through the National Environment Programme.

The status log of a permit sets out the permitting history, including any changes to the permit reference number. It is not backdated before 6 April 2010.

Status log of the permit		
Description	Date	Comments
Permit modified 011560/V001	18/03/2013	Storm tank volume corrected.
Variation determined 011560/V002	29/03/2016	Variation of permit initiated under PR14 review programme to incorporate improvements to be delivered under AMP6. Varied and consolidated permit issued in modern condition format.
Environment Agency initiated variation 011560/V003	01/04/2016	Variation of permit initiated under to deliver the requirements of the Bristol Avon project.
Variation determined 011560	30/12/2016	Varied and consolidated permit issued in modern condition format.

End of introductory note

Notice of variation and consolidation

The Environmental Permitting (England and Wales) Regulations 2010

The Environment Agency in exercise of its powers under regulation 20 of the Environmental Permitting (England and Wales) Regulations 2010 varies and consolidates

Permit number

011560

Issued to

Wessex Water Services Limited (“the operator”)

whose registered office is

Wessex Water Operations Centre

Claverton Down Road

Claverton Down

Bath

BA2 7WW

company registration number 02366648

to operate a water discharge activity at

Rode Wastewater Treatment Works

Rode Hill

Frome

Somerset

BA11 6PS

to the extent set out in the schedules.

The notice shall take effect from 01/01/2017.

Name	Date
Suzanne Haworth	30/12/2016

Authorised on behalf of the Environment Agency

Schedule 1

Only conditions 2.3.2(e), 3.3.4, 3.3.7, Schedule 1 Table S1.2, Schedule 3 Table S3.1, S3.2 and S3.4, Schedule 4 Table S4.1 and S4.2 and Schedule 7 have been varied by the consolidated permit 011560 as a result of an Environment Agency initiated variation.

Schedule 2 – consolidated permit

Consolidated permit issued as a separate document.

Permit

The Environmental Permitting (England and Wales) Regulations 2010

Permit number

011560

This is the consolidated permit referred to in the variation and consolidation notice for variation 011560/V003 authorising,

Wessex Water Services Limited (“the operator”)

whose registered office is

Wessex Water Operations Centre

Claverton Down Road

Claverton Down

Bath

BA2 7WW

company registration number 02366648

to operate a water discharge activity at

Rode Wastewater Treatment Works

Rode Hill

Frome

Somerset

BA11 6PS

to the extent authorised by and subject to the conditions of this permit.

Name	Date
Suzanne Haworth	30/12/2016

Authorised on behalf of the Environment Agency

Conditions

1 Management

1.1 General management

- 1.1.1 The operator shall manage and operate the activities:
- (a) in accordance with a written management system that identifies and minimises risks of pollution so far as is reasonably practicable, including those risks arising from operations, maintenance, accidents, incidents, non-conformances and those drawn to the attention of the operator as a result of complaints; and
 - (b) using sufficient competent persons and resources.
- 1.1.2 Records demonstrating compliance with condition 1.1.1 shall be maintained.
- 1.1.3 Any person having duties that are or may be affected by the matters set out in this permit shall have convenient access to a copy of the permit.

2 Operations

2.1 Permitted activities

- 2.1.1 The only activities authorised by the permit are the activities specified in schedule 1 table S1.1.

2.2 The site

- 2.2.1 The discharge activities shall take place at the discharge points marked on the site plans at schedule 7 to this permit, and as listed in table S3.2; and, the operating techniques that are the subject of conditions prefixed by 2.3 shall be applied at the locations shown, or otherwise described, in schedule 7.

2.3 Operating techniques

- 2.3.1 For the activity A1 referenced in schedule 1, table S1.1 the activity shall, subject to the conditions of this permit, be operated using the techniques and in the manner described in the documentation specified in schedule 1, table S1.2, unless otherwise agreed in writing by the Environment Agency.
- 2.3.2 If notified by the Environment Agency that the activities are giving rise to pollution, the operator shall submit to the Environment Agency for approval within the period specified, a revision of any plan or other documentation ("plan") specified in schedule 1, table S1.2 which identifies and minimises the risks of pollution relevant to that plan, and shall implement the approved revised plan in place of the original from the date of approval, unless otherwise agreed in writing by the Environment Agency.
- 2.3.3 For the activity A1 referenced in schedule 1, table S1.1 the operator shall comply with the relevant requirements of the Urban Waste Water Treatment (England and Wales) Regulations 1994.
- 2.3.4 For the discharge(s) specified in table S3.3:
- (a) The discharge shall only occur when and only for as long as the flow passed forward is equal to or greater than the overflow setting indicated due to rainfall and/or snow melt.
 - (b) Off-line storm storage must be fully utilised before a discharge occurs. It shall only fill when the flow passed forward is equal to or greater than the overflow setting indicated due to rainfall and/or snow melt and shall be emptied and its contents returned to the continuation flow as

soon as reasonably practicable. The minimum off-line storm storage required is specified in table S3.3.

- (c) The discharge shall not be comminuted or macerated and shall have passed through screens as specified and shall not contain a significant quantity of solid matter with a particle size greater than any indicated. All screenings shall be removed from the discharge.
- (d) Where a mechanically cleaned screen is installed, a telemetry alarm system shall be installed and maintained, as far as reasonably practicable, so as to give the operator immediate notification of a failure of the screen cleaning mechanism, unless otherwise agreed in writing by the Environment Agency. The operator shall take all appropriate measures to return the screen cleaning mechanism to normal operation as soon as reasonably practicable after receipt of notification of the failure.
- (e) Event duration monitoring telemetry equipment shall be installed and maintained, as far as reasonably practicable, so as to give the operator notification as soon as reasonably practicable, of a failure of the event duration monitoring equipment, unless otherwise agreed in writing by the Environment Agency. The operator shall take all appropriate measures to return event duration monitoring equipment to normal operation as soon as reasonably practicable after receipt of notification of the failure.

3 Emissions and monitoring

3.1 Emissions to water

3.1.1 The limits given in schedule 3 table S3.1 shall not be exceeded.

3.1.2 The limits in schedule 3 table S3.1 to which this condition applies may be exceeded where: in any series of samples of the discharge taken at regular but randomised intervals in any period of twelve consecutive months as listed in column 1 of schedule 3A, no more than the relevant number of samples, as listed in column 2 of schedule 3A, exceed the applicable limit for that relevant parameter.

3.1.3

- (a) For the emission limits in schedule 3 table S3.1 to which this condition applies, no sample of the discharge taken at a time when unusual weather conditions are adversely affecting the operation of the waste water treatment works, shall be taken into account in deciding whether or not the emission limit has been complied with.
- (b) On any occasion where unusual weather conditions adversely affect the operation of the waste water treatment works, the operator shall use its best endeavours to mitigate that adverse effect.
- (c) For any sample of the discharge taken to be considered for the purposes of (a) above, the operator shall notify the Environment Agency in writing within 14 days of becoming aware that an emission limit has been exceeded. That notification shall include a full description of the unusual weather conditions and their impact on the operation of the works.

3.1.4

- (a) If the measured Dry Weather Flow exceeds the permitted Dry Weather Flow limit then the operator shall, as soon as is practicable, investigate the reasons for the exceedance. The operator shall report the reasons for the exceedance to the Environment Agency and the steps that it proposes to take to restore compliance. An exceedance of the Dry Weather Flow limit shall not be recorded as a failure if the operator takes appropriate steps to restore compliance;
- (b) If the measured Dry Weather Flow exceeds the permitted Dry Weather Flow limit because of unusual rainfall during the 12-month period, then it will not be recorded as a failure of the Dry Weather Flow limit. For the purposes of this condition, unusual rainfall shall mean rainfall that

causes significantly higher sewage flows during the three-month period that normally records the lowest flows;

- (c) The permitted Dry Weather Flow limit is set at the operator's planned annual 80% exceeded flow;
- (d) For compliance with this permit, the measured Dry Weather Flow is that total daily volume that is exceeded by 90% of the recorded measured total daily volume values in any period of 12 months; and
- (e) For unusual rainfall to be considered, the operator shall notify the Environment Agency and provide supporting evidence as part of the normal specified data returns.

3.2 Emissions of substances not controlled by emission limits

3.2.1 For the activity A1 referenced in schedule 1, table S1.1 the operator shall take appropriate measures to minimise so far as reasonably practicable the polluting effects of the emissions of substances in the discharge not controlled by emission limits (excluding odour).

3.3 Monitoring

3.3.1 The operator shall, unless otherwise agreed in writing by the Environment Agency, undertake the monitoring specified in the following tables in schedule 3 to this permit:

- (a) point source emissions specified in tables S3.1 and S3.4.

3.3.2 The operator shall maintain records of all monitoring required by this permit.

3.3.3 Monitoring equipment, techniques, personnel and organisations employed for the emissions monitoring programme and the environmental or other monitoring specified in condition 3.3.1 shall have either MCERTS certification or MCERTS accreditation (as appropriate), where available, unless otherwise agreed in writing by the Environment Agency.

3.3.4 Accessible monitoring points shall be provided and maintained to enable the emissions monitoring programme and/or other monitoring to be carried out at the monitoring points specified in table S3.4 of schedule 3 and shown marked on the site plan in schedule 7.

3.3.5 The monitoring programme for the parameters subject to schedule 3B shall be:

- (a) pre-scheduled to cover a calendar year and the programme recorded before the start of a calendar year sample period; and
- (b) spot samples collected at approximately equal intervals during the year, including samples from different days of the week and different times. Approximately 10% of samples should be outside the normal sampling window which is 9am-3pm, Monday to Friday.

3.3.6 After becoming aware, or following a notification that a sample has not been taken on the schedule 3B Monitoring Programme pre-scheduled date, or is lost, or a result for that sample cannot be reported, the operator shall record the details and reschedule the sample.

3.3.7 For the activity A2 referenced in schedule 1, table S1.1 an event duration monitoring telemetry system shall be installed and maintained, as far as reasonably practicable so as to give the operator data available of discharge occurrence (start and stop) at the frequency defined in table S3.1.

4 Information

4.1 Records

4.1.1 All records required to be made by schedule 3, 4 and 5 to this permit shall:

- (a) be legible;

- (b) be made as soon as reasonably practicable;
- (c) if amended, be amended in such a way that the original and any subsequent amendments remain legible, or are capable of retrieval; and
- (d) be retained, unless otherwise agreed in writing by the Environment Agency, for at least 6 years from the date when the records were made.

4.1.2 The operator shall maintain convenient access, in either electronic or hard copy, to the records, plan and management system required to be maintained by this permit.

4.2 Reporting

4.2.1 The operator shall send all reports and notifications required by the permit to the Environment Agency using the contact details supplied in writing by the Environment Agency.

4.2.2 Within the time period after the end of the reporting period specified in schedule 4 table S4.1 the operator shall, unless otherwise agreed in writing by the Environment Agency, submit reports of the monitoring and assessment carried out in accordance with the conditions of this permit, as follows:

- (a) in respect of the parameters and monitoring points specified in schedule 4 table S4.1;
- (b) for the reporting periods specified in schedule 4 table S4.1 and using the forms specified in schedule 4 table S4.2; and
- (c) giving the information from such results and assessments as may be required by the forms specified in those tables.

4.3 Notifications

4.3.1 The Environment Agency shall be notified as soon as reasonably practicable following detection, within the site of the regulated facility of:

- (a) any malfunction, breakdown or failure of equipment or techniques, accident, or emission of a substance not controlled by an emission limit which has caused, is causing or may cause significant pollution; and
- (b) any breach of a limit specified in schedule 3 table S3.1 (including individual exceedances of limits which are covered by condition 3.1.2).

Any other significant adverse environmental effects, which may have been caused by the activity, shall also be notified to the Environment Agency as soon as reasonably practicable following detection.

4.3.2 The information provided under condition 4.3.1 shall be supported by sending the information listed in schedule 5 to this permit within the time period specified in that schedule.

4.3.3 Where the Environment Agency has requested in writing that it shall be notified when the operator is to undertake monitoring and/or spot sampling specified in schedule 3B, the operator shall inform the Environment Agency when the relevant monitoring and/or spot sampling is to take place. The operator shall provide this information to the Environment Agency at least 14 days before the date the monitoring is to be undertaken.

4.3.4 The Environment Agency shall be notified within 14 days of the occurrence of the following matters, except where such disclosure is prohibited by Stock Exchange rules:

Where the operator is a registered company:

- (a) any change in the operator's trading name, registered name or registered office address; and
- (b) any steps taken with a view to the operator going into administration, entering into a company voluntary arrangement or being wound up.

Where the operator is a corporate body other than a registered company:

- (a) any change in the operator's name or address; and
- (b) any steps taken with a view to the dissolution of the operator.

4.3.5 For the activity A1 referenced in schedule 1, table S1.1 where the operator proposes to make a change in the nature of the activity by increasing the concentration of, or the addition of, or allowing the introduction of, a substance to the activity to an extent that the operator considers could have a significant adverse environmental effect on the receiving waters, and the change is not permitted by emission limits specified within schedule 3 table S3.1 or the subject of an application for approval under the EP Regulations or under the terms of this permit:

- (a) the Environment Agency shall be notified in writing at least 14 days before the increase or addition or allowing the introduction; and
- (b) the notification shall contain a description of the proposed change.

4.4 Interpretation

4.4.1 In this permit the expressions listed in schedule 6 shall have the meaning given in that schedule.

4.4.2 In this permit references to reports and notifications mean written reports and notifications, except where reference is made to notification being made "as soon as reasonably practicable", in which case it may be provided by telephone.

Schedule 1 – Operations

Table S1.1 Activities		
Activity reference	Description of activity	Limits of specified activity
A1	Discharge of secondary treated sewage effluent via Outlet 1	N/A
A2	Discharge of settled storm sewage via Outlet 2	N/A

Table S1.2 Operating techniques			
Activity reference	Description of documentation	Parts	Date Received
A1	BA OTA1 - Bristol Avon Catchment Permitting for Phosphorus Operating Techniques Agreement Document	All	09/03/2016

Schedule 2 – Waste types, raw materials and fuels

Schedule 2 not in use.

Schedule 3 – Emissions and monitoring

Table S3.1 Point Source emissions to water (other than sewer) – emission limits and monitoring requirements						
Effluent(s) and discharge point(s)	Parameter	Limit (including unit)	Reference Period	Limit of effective range	Monitoring frequency	Compliance Statistic
A1 Secondary treated sewage effluent via Outlet 1	Dry weather flow	230 m ³ /day	Total daily volume	N/A	Continuous	Condition 3.1.4 applies
	15-minute instantaneous or averaged flow	No limit set. Record as l/s	15 minute	N/A	Continuous	N/A
	ATU-BOD as O ₂	20 mg/l	Instantaneous (spot sample)	N/A	As specified in schedule 3B	Look up table (Conditions 3.1.2 and 3.1.3 apply)
	Ammoniacal nitrogen (expressed as N)	10 mg/l	Instantaneous (spot sample)	N/A	As specified in schedule 3B	Look up table (Conditions 3.1.2 and 3.1.3 apply)
	Suspended solids (measured after drying at 105°C)	40 mg/l	Instantaneous (spot sample)	N/A	As specified in schedule 3B	Look up table (Conditions 3.1.2 and 3.1.3 apply)
	Visible oil or grease	No significant trace present so far as is reasonably practicable	Instantaneous (visual examination)	N/A	N/A	No significant trace (Condition 3.1.3 applies)
A2 Settled storm sewage via Outlet 2	Settled storm sewage discharge event duration monitoring (discharge / no discharge)	N/A	N/A	Condition 3.3.3 does not apply	2 minute	N/A
	Settled storm	N/A	N/A	Condition 3.3.3 does not apply	Whenever a	N/A

Table S3.1 Point Source emissions to water (other than sewer) – emission limits and monitoring requirements						
Effluent(s) and discharge point(s)	Parameter	Limit (including unit)	Reference Period	Limit of effective range	Monitoring frequency	Compliance Statistic
	sewage discharge start and end times				discharge occurs	
	Settled storm sewage discharge event duration monitoring status (operational / not operational)	N/A	N/A	Condition 3.3.3 does not apply	2 minute	N/A

Effluent Name	Discharge Point	Discharge point NGR	Receiving water/Environment
A1 Secondary treated sewage effluent	Outlet 1	ST 80410 54560	River Frome
A2 Settled storm sewage	Outlet 2	ST 80395 54549	River Frome

Effluent(s) and discharge point(s)	Description of discharge	Overflow setting l/s	Maximum size of solid matter	Screen aperture size	Minimum screen capacity flow l/s	Minimum storage capacity m³ (off line)
A2 Settled storm sewage via Outlet 2	Settled storm sewage	6.1	No greater than 6 mm in more than 1 dimension	6 mm x 6 mm	The screen shall be designed to cope with all flows up to and including the 1 in 5 year storm return period, as a minimum	46

Effluent(s) and discharge point(s)	Monitoring type	Monitoring point NGR	Monitoring point reference
A1 Secondary treated sewage effluent via Outlet 1	Effluent monitoring	ST 80412 54553	M1
A1 Secondary treated sewage effluent via Outlet 1	MCERTS flow monitoring	ST 80412 54553	M3
A2 Settled storm sewage via Outlet 2	Effluent monitoring	ST 80397 54545	M2
A2 Settled storm sewage via Outlet 2	Event duration monitoring	ST 80397 54545	M2

Schedule 3A - Look up table

Look up table	
Number of samples taken in any period of 12 months	Maximum number of samples permitted to exceed limit for given parameter
4-7	1
8-16	2
17-28	3
29-40	4
41-53	5
54-67	6
68-81	7
82-95	8
96-110	9
111-125	10
126-140	11
141-155	12
156-171	13
172-187	14
188-203	15
204-219	16
220-235	17
236-251	18
252-268	19
269-284	20
285-300	21
301-317	22
318-334	23
335-350	24
351-365	25

Schedule 3B - OSM tier 3 sampling frequency

Parameter	'Normal frequency' of samples per year	Reduced Sampling frequency after 12 consecutive months of numeric permit compliance, samples per year or pro rata over the remainder of a year	On numeric limit failure return to normal frequency as soon as reasonably practicable, samples per 12 months ¹	Out of hours samples
Sanitary	24	12	24	For 24 samples 2 out of hours samples per annum
Non sanitary	12	12	12	For 12 samples 1 out of hours sample per annum

¹For UV efficacy monitoring use sanitary frequency and increase following failure of UV requirements only.

Schedule 4 – Reporting

Parameters, for which reports shall be made, in accordance with conditions of this permit, are listed below.

Table S4.1 Reporting of monitoring data			
Parameter	Monitoring point reference	Reporting period	Period begins
Dry Weather Flow (daily flows total)	M3	Annually Report to be submitted within 2 months of the end of the calendar year	1 January
15-minute flow	M3	Reports to be provided to the Environment Agency upon request Report to be submitted within 28 days unless otherwise specified in writing by the Environment Agency	Upon request by the Environment Agency
Operator Self Monitoring - ATU-BOD as O ₂ , ammoniacal nitrogen (expressed as N), suspended solids (measured after drying at 105°C)	M1	Quarterly Report to be submitted within 28 days	1st of month
Operator Self Monitoring summary report	M1	Annually Report to be submitted within 2 months of the end of the calendar year	1 January
Settled storm sewage discharge start and end times	M2	Reports to be provided to the Environment Agency upon request Report to be submitted within 28 days unless otherwise specified in writing by the Environment Agency	Upon request by the Environment Agency
Settled storm sewage discharge start and end times	M2	Annually Report to be submitted within 2 months	1 January

Table S4.1 Reporting of monitoring data			
Parameter	Monitoring point reference	Reporting period	Period begins
Settled storm sewage discharge event duration monitoring status (operational / not operational)	M2	Annually Report to be submitted within 2 months	1 January

Table S4.2 Reporting forms	
Parameter	Reporting format
Dry Weather Flow (daily flows total)	WISKI electronic format specified by the Environment Agency
15-minute flow	WISKI electronic format specified by the Environment Agency
OSM - ATU-BOD as O ₂ , ammoniacal nitrogen (expressed as N), suspended solids (measured after drying at 105°C)	Quarterly - Electronic format specified by the Environment Agency
Operator Self Monitoring summary report	Annually - Summary report of compliance with the monitoring programme specified in Table S3.1 and schedule 3B in a format specified by the Environment Agency
Settled storm sewage discharge start and end times	Form as agreed in writing by the Environment Agency
Settled storm sewage discharge start and end times	Annual summary report or other form as agreed in writing by the Environment Agency Number of and total duration of counted spills for all spills.
Settled storm sewage discharge event duration monitoring status (operational / not operational)	Annual summary report or other form as agreed in writing by the Environment Agency Percentage of time in the reporting period that the event duration monitoring equipment was operational.

Schedule 5 – Notification

These pages outline the information that the operator must provide.

Units of measurement used in information supplied under Part A and B requirements shall be appropriate to the circumstances of the emission. Where appropriate, a comparison should be made of actual emissions and authorised emission limits.

If any information is considered commercially confidential, it should be separated from non-confidential information, supplied on a separate sheet and accompanied by an application for commercial confidentiality under the provisions of the EP Regulations.

Part A

Permit Number	
Name of operator	
Location of Facility	
Time and date of the detection	

(a) Notification requirements for any malfunction, breakdown or failure of equipment or techniques, accident, or emission of a substance not controlled by an emission limit which has caused, is causing or may cause significant pollution	
To be notified within 7 days of detection unless otherwise agreed in writing by the Environment Agency	
Date and time of the event	
Reference or description of the location of the event	
Description of where any release into the environment took place	
Substances(s) potentially released/type or nature of sewage released	
Best estimate of the quantity or rate of release of substances and/or duration of discharge	
Best estimate of the environmental impact of the discharge	
Measures taken, or intended to be taken, to stop any emission	
Description of the failure or accident.	

(b) Notification requirements for the breach of a limit specified in schedule 3 table S3.1 (including individual exceedances of limits which are covered by condition 3.1.2)	
The information specified below is to be notified to the Environment Agency as soon as reasonably practicable following detection.	
Monitoring point reference/ source	
Self monitoring regime (where relevant)	e.g. OSM
Type of failure	e.g. LUT failure/LUT exceedance
Date of sample/event	
Parameter	
Result and units	
Limit and units	

Part B – to be submitted as soon as reasonably practicable unless otherwise agreed in writing by the Environment Agency

Any more accurate information on the matters for notification under Part A.	
Measures taken, or intended to be taken, to prevent a recurrence of the incident/breach/exceedance	
Measures taken, or intended to be taken, to rectify, limit or prevent any pollution of the environment which has been or may be caused by the emission	

Name*	
Post	
Signature	
Date	

* authorised to sign on behalf of the operator

Schedule 6 – Interpretation

“accident” means an accident that may result in pollution.

"annually" means once every year.

“application” means the application for this permit, together with any additional information supplied by the operator as part of the application and any response to a notice served under Schedule 5 to the EP Regulations.

For the activity A1 referenced in schedule 1, table S1.1 “appropriate measures” for the purposes of the emission of substances not controlled by emission limits condition (condition 3.2.1) do not require the operator to undertake treatment to a level beyond that specified in schedule 1 table S1.1, or to carry out routine monitoring for substances not controlled by emission limits.

“ATU-BOD as O₂” means the biochemical oxygen demand (measured after 5 days at 20°C with nitrification suppressed by the addition of allylthiourea).

“emissions of substances not controlled by emission limits” means emissions of substances to air, water or land from the permitted activities, which are not controlled by an emission limit.

“EP Regulations” means The Environmental Permitting (England and Wales) Regulations SI 2010 No.675 and words and expressions used in this permit which are also used in the Regulations have the same meanings as in those Regulations.

“MCERTS” means the Environment Agency’s Monitoring Certification Scheme.

“minimum screen capacity flow” means the minimum flow passed through the screens to the outfall when the screen bypass operates.

“monitoring frequency” as used in Table S3.1 in the context of Event Duration Monitoring is the temporal interval at which a change of state between no discharge and discharge is to be detected.

“overflow” for the purposes of schedule 7, means any weir or orifice or other means via which flow in excess of its overflow setting is diverted from the continuation sewer when it is caused by rainfall and or snowmelt.

“overflow setting” means the minimum flow passed forward to the continuation flow when the overflow operates.

"quarter" means a calendar year quarter commencing on 1 January, 1 April, 1 July or 1 October.

“significant pollution” means a category 1 or category 2 incident indicated by the Common Incident Classification Scheme (CICS).

“spill” one or more overflow events within a period of 12 hours or less will be considered to be one spill, one or more overflow events extending over a period of greater than 12 hours up to 36 hours will be considered to be 2 spills. Each subsequent 24 hour duration counts as 1 additional spill and the whole of the 24 hour block is included.


“unusual weather conditions” includes, but is not limited to:

- low ambient temperatures, or the freezing of mechanical equipment in the works;
- significant snow deposits;
- tidal or fluvial flooding;
- weather conditions causing unforeseen loss of power supply to the sewage treatment that could not be ameliorated by the reasonable provision and operation of standby generation facilities.

“Urban Waste Water Treatment (England and Wales) Regulations 1994 (UWWTR)” means Urban Waste Water Treatment (England and Wales) Regulations 1994 SI 2841 and the words and expressions used in this permit which are also used in the Regulations have the same meanings as in those Regulations.

“year” means calendar year ending 31 December.

Schedule 7 – Site plans



Levex Water
a YTL company

13256
RODE
Sewage Treatment Works
LOCATION PLAN
Centre: 380,456 154,592


Scale: 1:5000
Printed on: 09/11/2016 16:11

WASTE NETWORK LEGEND				
STRUCTURES	<ul style="list-style-type: none"> Manhole - Full Manhole - Surface Manhole - Combined Outlet Islet Landslide Branchion - Full Branchion - Surface Branchion - Combined Confined Storage Chamber Pumping Station - Surface Pumping Station - Four-Combined 	<ul style="list-style-type: none"> Quill Vert Column Rodding Eye Catchpit Flushing Chamber Stackway Man-Robot Valve Air Valve Weathered HAZI-Box Other 	<ul style="list-style-type: none"> Public Sewer Surface Water Sewer Combined Sewer Man/Men Septic Overflow Low-Pressure 	<ul style="list-style-type: none"> Private Sewer Chain Highway Drain Coloured/Potterware Abandoned Sewer Status Unknown Section 131 - Full Section 131 - Surface Section 131 - Combined Private Rising Main Other (Unspecified)
BOUNDARIES	<ul style="list-style-type: none"> Section 134 Site 	OTHER STRUCTURES	<ul style="list-style-type: none"> Allocation Tank Storage Tank Chamber Tunnel Interceptor 	

Information in this plan is provided for identification purposes only. No warranty as to accuracy is given or implied. The precise route of pipe work may not exactly match that shown. Where there does not appear to be a sewer or other structure shown, it is not shown. You are advised to commence investigations using hand tools only. Mechanical digging equipment should not be used until pipe work has been precisely located.

If you are considering any form of building works and pipe work is shown within the boundary of your property or a property to be purchased (or very close by) a surveyor should plot the exact position prior to commencing work or purchase. Building over or near Wastewater. Wate's approval is not normally permitted.

Reproduced from the Ordnance Survey Map with the permission of the Controller of the Majesty's Stationery Office. Crown copyright reserved. Licence No. 1000180738





13256
RODE
Sewage Treatment Works
SITE PLAN
Centre: 380,456 154,592

Scale: 1:650
Printed on: 08/11/2016 14:54

WASTE NETWORK LEGEND

<p>STRUCTURES</p> <ul style="list-style-type: none"> Manhole - Foot Manhole - Surface Manhole - Combined Outlet Inlet Landfill Diffraction - Foot Diffraction - Surface Diffraction - Combined Combined Sewage Overflow Pumping Station - Surface Pumping Station - Foot/Combined <p>BOUNDARIES</p> <ul style="list-style-type: none"> Section 154 Site 	<ul style="list-style-type: none"> Quill Valve Column Rolling Eye Castoff Rainwater Chamber Sanitary New Water Valve Air Valve Valvehead Manhole Other <p>OTHER STRUCTURES</p> <ul style="list-style-type: none"> Abandonment Tank Storage Tank Chamber Tank Invertor 	<p>PUBLIC SEWERS</p> <ul style="list-style-type: none"> Foot Sewer Surface Water Sewer Combined Sewer Rain/Mean Overfall Use Limitation <p>NON-PUBLIC SEWERS & PIPELINES</p> <ul style="list-style-type: none"> Private Sewer/Drain Highway Drain Combined Watercourse Abandoned Sewer State Un-known Section 154 - Foot Section 154 - Surface Section 154 - Combined Private Sewer/Drain 	<p>Information in this plan is provided for identification purposes only. No warranty as to accuracy is given or implied. The precise route of pipe work may not exactly match that shown. Wastewater does not accept liability for inaccuracies.</p> <p>Sewers and lateral drains adopted by Wastewater under the Water Industry (Schemes for Adoption of Private Sewers) Regulations 2011 are to be marked over time and may not yet be shown.</p> <p>In carrying out any works, you accept liability for the cost of any repairs to Wastewater (lateral drains) damaged as a result of your works. You are advised to commence excavations using hand tools only. Mechanical digging equipment should not be used until pipe work has been precisely located.</p> <p>If you are considering any form of building works and pipe work shown within the boundary of your property or a property to be purchased (or any other) a surveyor should give the exact position prior to commencing works or purchase. Building over or near Wastewater's property is not normally permitted.</p> <p>Reproduced from the Ordnance Survey Map with the permission of the Controller of Her Majesty's Stationery Office. Crown copyright reserved. (Source No. 100144234)</p>
--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

END OF PERMIT

Permit number
011560