

OXFORDSHIRE COUNTY COUNCIL
LOCAL GOVERNMENT ACT, 1972
CONTROL OF POLLUTION ACT, 1974

WASTE DISPOSAL LICENCE SUBJECT TO CONDITIONS

Holder of Licence (Name and Address)	Controlled Reclamation (Oxford) Ltd., Enslow, Bletchington, Oxford.
Date of Original Application	21st January 1985
Location of Facility	Gravel Works at Stanton Harcourt Parcel Number 1620 and Part Parcel Numbers 0018 and 6562
Ordnance Survey Grid Reference	SP 404 054
Brief Particulars of Proposals	Deposit of Inert Solid Materials.
Type of Facility	Landfill
Waste Disposal Licence No.	OCC/64/M/01

The OXFORDSHIRE COUNTY COUNCIL as Waste Disposal Authority HEREBY AUTHORISE THE deposit of controlled waste as described in your application and the plans accompanying such application, subject to the conditions set out in the Schedule of Conditions appended hereto.

Original Licence OCC/64
DATED: 30th May 1985

County Solicitor

Modification OCC/64/M/01
Granted 25th March 1986.



YOUR ATTENTION IS DRAWN TO THE NOTES OVERLEAF



IMPORTANT NOTICE

1. APPEAL PROCEDURE

If the licence holder is aggrieved by the decision of the Waste Disposal Authority in granting the licence subject to conditions he may appeal to the Secretary of State in accordance with Section 10 of the Control of Pollution Act, 1974. Appeals must be notified within 6 months of the date of this notice to the Secretary, Department of the Environment, Waste Management Division, 43 Marsham Street, London, SW1 3PY. The Secretary of State has power to allow a longer period for the giving of notice of an appeal but he will not normally be prepared to exercise this power unless there are special circumstances which excuse the delay in giving notice of an appeal.

2. OBLIGATIONS UNDER OTHER LEGISLATION

The issue of this licence does not affect in any way the licence holder's statutory obligations under other legislation (in particular those set out in the Health and Safety at Work etc., Act, 1974; the Radioactive Substances Act, 1960, the legislation covering Planning, Water Protection and Environmental Health) and offences under such legislation would render the licence holder liable for prosecution.

TABLE OF CONTENTS

100.	<u>THE WASTE</u>
101.	Permitted Types and Quantities
102.	Commencement and Cessation of Tipping
200.	<u>PREPARATORY WORKS</u>
202.	Fencing and Gates
203.	Protective Clay Lining
204.	Drainage
205.	Earthworks
206.	Roadworks
207.	Boreholes and Inspection Manholes
208.	Site Control Office
209.	Site Information Boards
211.	Wheelwash
300.	<u>WORKING PLAN</u>
301.	Submission of Working Plan
302.	Specification of Working Plan
400.	<u>OPERATIONAL SPECIFICATION</u>
401.	Superintendence of Site Operations
402.	Maintenance of Works
403.	Covering of Waste
404.	Formation of Layers
405.	Compaction of Waste
406.	Settlement
410.	Tidy Condition of Site
412.	Final Layer
413.	Pest Control
414.	Fire Precautions
415.	Dust
416.	Noise
418.	Mud or Waste on Highways
419.	Topsoil
420.	Protection of Water Systems
423.	Site to be kept dry
424.	Site Roads
425.	Security of Site
427.	Site Records
428.	Asbestos
429.	Dewatering
460.	Site Manning
462.	Site Control
464.	Tidy Condition of Site Entrance
465.	Deposit of Waste in Water.
466.	Setting out of Tipping Areas

100. THE WASTE

101. Permitted Types and Quantities

The types and quantities of waste to be deposited daily at the site shall not exceed the following:-

- (1) 200 tonnes of commercial and industrial waste comprising only timber, glass, plastic and small quantities of paper and cardboard not exceeding 5% by volume of any single consignment of waste.
- (2) 650 tonnes of construction industry waste comprising only hardcore, broken brick, soil, rock and small quantities of high density asbestos.
- (3) 250 Tonnes of mine and quarry waste.

102. Permitted areas for Disposal

The areas within the site where disposal is permitted shall be as indicated on the plans accompanying the application. Only wastes included in 101 (2) and 101 (3) above may be deposited within 50 metres of the River Windrush.

200. PREPARATORY WORKS

202. Fencing and Gates

Prior to the commencement of tipping, fencing and secure gates shall be provided to the site, in all respects to the satisfaction of the Oxfordshire County Council.

203. Protective Clay Linings

Prior to the commencement of tipping in any area the sides of the site shall be lined by pushing clay from the site floor, the lining shall be fully continuous with the clay underlying the site.

All clay slopes shall be of minimum thickness of two metres and shall be well compacted and free of fissures.

The clay lining shall be constructed not less than two weeks in advance of filling in any area. The County Council and Thames Water Authority shall be notified in writing when the clay lining is ready for inspection. No tipping shall commence in that area of the site until the clay lining has been approved by the County Council.

204. Drainage

Prior to the commencement of tipping and subsequently, all measures necessary to remove excess water from the tipping area shall be taken to the satisfaction of the Oxfordshire County Council.

205. Earthworks

Prior to the commencement of tipping in any area, screening embankments of minimum height 2.5 metres shall be constructed around the perimeter of that area, to the satisfaction of the Oxfordshire County Council. The external face of the embankments shall be seeded to the satisfaction of the Oxfordshire County Council.

206. Roadworks

Prior to the commencement of tipping a site road, hard standing and manoeuvring area shall be constructed from well compacted granular material. The site road, hard standing and manoeuvring area shall be constructed in all respects to the satisfaction of the Oxfordshire County Council.

207. Boreholes and Inspection Manholes

Monitoring boreholes shall be provided around the site at the location and to the specification agreed by the Thames Water Authority. Inspection manholes shall be provided within each tipping area to allow access to the floor of the site. The bases of the manholes shall be perforated to allow water to enter the manholes and perforated lockable covers shall be provided.

208. Site Control Office

Prior to the commencement of tipping, a site control office shall be provided to the satisfaction of the Oxfordshire County Council.

209. Site Information Boards

Prior to the commencement of tipping, a site information board shall be provided at the site entrance.

The site information board shall be made of durable material and finish. It shall state the name of the site, the name, address and telephone number of the operator and of the Oxfordshire County Council. It shall state that no unauthorised persons may enter the site.

The site information board shall be provided in all respects to the satisfaction of the Oxfordshire County Council.

211. Wheelwash

Prior to the commencement of tipping, a wheelwash shall be provided at the site exit at a location to be agreed with the Oxfordshire County Council and shall be constructed to the satisfaction of the County Council.

300. WORKING PLAN

301. Submission of Working Plan

No deposit of waste shall take place unless at least one month previously a working plan, giving details for the proposed conduct of operations at the site, has been submitted to the Oxfordshire County Council. The licence holder shall keep the Working Plan updated as necessary and shall forward a copy of each updated Working Plan to the Oxfordshire County Council.

302. Specification of Working Plan

The form and presentation of the plan shall be to the approval of the County Council. Two copies of the plan shall be provided to the County Council.

The following shall be clearly marked on the plan:-

- (i) The proposed layout of perimeter fencing and site gates.
- (ii) The proposed location of the site control office.
- (iii) The proposed location of the main site roads.
- (iv) The proposed sequence of filling together with an estimate of time required to complete each section of the works.
- (v) The direction of filling.
- (vi) The proposed method of filling including the number and depth of layers in each section of the works.
- (vii) The proposed maximum width of the working face.
- (viii) Details of proposed sources or reserves of cover material.
- (ix) Details of proposed arrangements to cater for the following:-
 - (i) Seasonal tipping
 - (ii) Filling in the event of an emergency
 - (iii) Filling in the event of wet weather

- (x) Details of site procedures to be followed:
 - (i) For the control of rats or other pests
 - (ii) In the event of fire
 - (iii) In the event of accidents
 - (iv) In the event of the discovery of unauthorised wastes.
- (xi) The proposed sequence of final restoration works together with an estimate of the time required to complete each section of the work.

400. OPERATIONAL SPECIFICATION

401. Superintendence of Site Operations

All necessary superintendence shall be provided for the satisfactory operation of the site, such superintendence being given by sufficient persons having adequate knowledge of the operations being carried out, including the methods and techniques required, the hazards likely to be encountered and methods of preventing accidents.

The terms of the site licence shall be made known to any person who is given responsibility for the management or control of the site. The Oxfordshire County Council shall be informed in writing of the name of the person directly responsible for ensuring that the site is operated in accordance with the terms of the licence.

A copy of the licence and the working plan and all subsequent amendments shall be displayed at the site control office.

402. Maintenance of Works

All the preparatory works referred to under the heading :
200. Preparatory Works, shall be properly protected and maintained at all times in all respects to the satisfaction of the Oxfordshire County Council.

403. Covering of Waste

- (i) As soon as possible after the deposit of waste other than inert waste, it shall be suitably covered on all surfaces exposed to the air with a minimum of 150mm of suitable non-putrescible material and during the formation of the layer not more than 50 square metres shall be left uncovered at any one time.
- (ii) No such waste shall be left uncovered at the end of any day.

404. Formation of Layers

- (i) Waste shall be consolidated and formed into layers using a tractor, bulldozer or other suitable machine equipped with a blade or other appropriate levelling device.
- (ii) The depth of any one layer of waste shall not after initial compaction exceed 2.0 m.
- (iii) Each layer of waste and covering material shall be laid to a fall sufficient to ensure the removal of surface water and the prevention of ponding.

405. Compaction of Waste

- (i) Waste shall be either (a) deposited on the surface of the site behind the face and partially compacted by a tractor, bulldozer or other compacting machine before being pushed over the face or (b) deposited on the ground forming the base of the site or on a previous layer in front of the face and formed into a compacted layer by being pushed upwards and driven over by a tractor, bulldozer or other compacting machine.
- (ii) The working face and flanks of any formation of waste deposited in accordance with this Condition shall not exceed an angle of 30° to the horizontal.

406. Settlement

Unless authorised in writing by the County Council, a period of not less than 3 months shall elapse between the placing of subsequent layers of waste.

410. Tidy Condition of Site

Loose waste, tins, bottles etc. which may be lying on or around the site or in the vicinity of the site shall be collected and removed or otherwise disposed of by the end of each working day or more frequently if necessary so that the site is maintained in a tidy condition. Until the final restoration of the site, completed areas of landfilling shall be graded and maintained in a tidy condition and where necessary action shall be taken to control or destroy weeds.

412. Final Layer

The final layer of waste deposited shall be subject to the minimum compaction and shall, to a depth of not less than 1 m, be kept free of materials likely to interfere with the final restoration or subsequent cultivation of the site.

413. Pest Control

A pest control programme shall be carried out in accordance with the working plan and in all respects to the satisfaction of the Oxfordshire County Council who shall be notified of any sign of infestation.

414. Fire Precautions

- (i) Site staff shall be properly instructed in the control of fires and the fire prevention procedures set out in the working plan shall be adhered to in all respects to the satisfaction of the Oxfordshire County Council.
- (ii) No waste shall be burnt within the boundaries of the site.
- (iii) Outbreaks of fire shall be notified to the Oxfordshire County Council within two working days of the outbreak.

415. Dust

All measures necessary to prevent dust rising and causing a nuisance shall be taken in all respects to the satisfaction of the Oxfordshire County Council.

416. Noise

All measures necessary to ensure that noise is kept to a minimum at all times shall be taken in all respects to the satisfaction of the Oxfordshire County Council.

418. Mud or Waste on Highways

Highways in the vicinity of the site shall be kept clear at all times of dirt, mud or any other debris arising from any operation on the site. Any deposits of dirt, mud or any other debris on nearby highways or surrounding land caused by operations shall be removed forthwith. If required by the County Council the site shall be closed until such time as the requirements of this condition can be complied with.

419. Topsoil

The stripping of topsoil shall be carried out in such a manner as to minimise wastage of topsoil. Topsoil thus stripped shall be retained on the site for use as final cover. Topsoil shall not be removed from the site without the prior written permission of the Oxfordshire County Council.

420. Protection of Water Systems

All measures necessary to prevent the pollution of surface or underground water systems shall be taken. The Oxfordshire County Council and the Regional Water Authority shall be notified immediately of any indication that pollution of water systems has occurred or that such pollution may be imminent.

423. Site to be kept dry

All measures necessary to maintain the area of the site in a dry state shall be taken in all respects to the satisfaction of the Oxfordshire County Council. Areas below the level of the winter water table are excepted from this requirement.

424. Site Roads

The site roads shall be maintained to a degree sufficient to permit vehicles to reach the tip face without difficulty.

425. Security of Site

All measures necessary to prevent the entry of unauthorised persons onto the site shall be taken in all respects to the satisfaction of the Oxfordshire County Council.

427. Site Records

A record shall be kept of the types and quantities of waste deposited at the site in a form prescribed by the Oxfordshire County Council. The record shall be available for inspection by the Oxfordshire County Council and a copy shall be forwarded to the Oxfordshire County Council at intervals to be determined by the Council.

428. Asbestos

Asbestos waste shall be disposed of in accordance with the recommendations of Waste Management Paper No. 18 published by the Department of the Environment and the current procedures of the Oxfordshire County Council for the disposal of Asbestos waste.

429. Dewatering

The Regional Water Authority and the Oxfordshire County Council shall be informed at least 3 days prior to the commencement of the dewatering of any part of the site.

No discharge shall occur to any watercourse or lake or into/onto any land unless consented by the Thames Water Authority.

460. Site Manning

A full time gateman and a full time machine operator shall be employed on the site during all opening hours. Suitable arrangements shall be made to provide relief staff on site to cover periods when permanent staff are absent due to holidays, sickness or any unforeseen circumstances.

462. Site Control

All vehicles entering the site shall report to the site control and shall not proceed into the site until authorised to do so by the gateman.

464. Tidy Condition of Site Entrance

The area adjacent to the site entrance shall be inspected at the beginning and end of each working day and all waste materials deposited shall be removed immediately following inspection and at more frequent intervals as may be necessary to maintain the entrance in a tidy condition.

465. Deposit of Waste in Water

Waste, other than clean excavated material, clean hardcore, broken brick and concrete shall not be deposited into water or within 7 metres of the edge of any area of ground water.

466. Setting out of Tipping Area

The area to be used for each week's tipping shall be set out in advance using marker pegs, in conformity with the working plan. The content of the working plan shall be explained in detail to the site staff and any revision to the working plan shall be discussed with the site staff.