

Rescanned Permit. All Conditions

Agency Ref No EAWML 42371
Modification No 3
Page 1 of 10

Redacted Conditions no longer applicable

**ENVIRONMENTAL PROTECTION ACT 1990
SECTION 37**

**WASTE MANAGEMENT LICENCE
NOTICE OF MODIFICATION**

LICENCE REF No: 201/1	FACILITY TYPE: Civic Amenity Site
LICENCE HOLDER: Leicestershire County Council County Hall Leicestershire County Council Dept of Highways, Transportation and Waste Management Glenfield Leicester Leicestershire LE3 8RJ	LICENSED FACILITY: Barwell Civic Amenity Site Stapleton Lane Barwell Hinckley LE9 8HD

WHEREAS on the 31 March 1993 the Leicestershire County Council issued a waste disposal licence (now to be treated as a waste management licence) in pursuance of its powers under Part 1 of the Control of Pollution Act 1974 for the above named facility to Paul Gunby and Karl Robert Damm

AND WHEREAS on the 1st April 1996 the powers and duties of all waste regulation authorities in England and Wales transferred to the Environment Agency ("the Agency") by virtue of section 2 of the Environment Act 1995

AND WHEREAS on the 29 April 1994 and the 4 ~~December~~ 2003 the said licence was modified

AND WHEREAS on the 31 March 1998 the said licence was transferred

NOTICE IS HEREBY GIVEN that the Agency modifies the conditions of the said licence in accordance with Section 37(1)(b) of the Environmental Protection Act 1990 and as set out in the Schedule attached to this notice.

Signed _____
Team Leader - I

Name Ian Brindley

Dated 10th November 2006

This modification shall take effect on 11th November 2006 at 00.01 hours

YOUR ATTENTION IS DRAWN TO THE RIGHTS OF APPEAL DETAILED AT THE END OF THIS MODIFICATION.

Environment Agency, Sentinel House, Wellington Crescent, Fradley Park, Lichfield, Staffs, WS13 8RR

EAWML 42371.

SCHEDULE – CONDITIONS RELATING TO THIS MODIFICATION

Modification of conditions under section 37(1)(b) as follows:

Delete existing conditions 3, 27 and appendices A, B, C, D, E and F

Add new conditions 28, 29, 30 and appendix G

28 General considerations

28.1 Specified waste management operations

- 28.1.1 No waste management operations shall be authorised by this licence unless:
- specified in and undertaken in accordance with the limitations in section 1.1.1 of the working plan and in the following table; or
 - otherwise required by the conditions of this licence as being an integral part of those operations:

Table 28.1 Specified waste management operations

Specified Waste Management Operation	Permitted Waste Types which may be subject to the Specified Operation	Limits on Specified Waste Management Operations
D15: Storage pending, on this site any of the category "D" operations authorised under this column, or elsewhere than on this site, any of the operations listed in Part III of Schedule 4 of the 1994 Regulations, (excluding temporary storage, pending collection, on the site where it is produced).	All wastes specified in Appendix G	Maximum storage capacity 305 tonnes, comprising no more than 10 tonnes of hazardous household waste for disposal and no more than 10 tonnes of waste oil. A site layout plan shall be maintained in accordance with condition 1.
R13: Storage of waste consisting of materials intended for submission, on this site to any of the category "R" operations authorised under this column, or elsewhere than on this site, to any of the operations listed in Part IV of Schedule 4 of the 1994 Regulations, (excluding temporary storage, pending collection, on the site where it is produced).		

SCHEDULE – CONDITIONS RELATING TO THIS MODIFICATION

Modification of conditions under section 37(1)(b) as follows:

Delete existing conditions 3, 27 and appendices A, B, C, D, E and F

Add new conditions 28, 29, 30 and appendix G

28 General considerations

28.1 Specified waste management operations

- 28.1.1 No waste management operations shall be authorised by this licence unless:
- specified in and undertaken in accordance with the limitations in section 1.1.1 of the working plan and in the following table; or
 - otherwise required by the conditions of this licence as being an integral part of those operations:

Table 28.1 Specified waste management operations

Specified Waste Management Operation	Permitted Waste Types which may be subject to the Specified Operation	Limits on Specified Waste Management Operations
D15: Storage pending, on this site any of the category "D" operations authorised under this column, or elsewhere than on this site, any of the operations listed in Part III of Schedule 4 of the 1994 Regulations, (excluding temporary storage, pending collection, on the site where it is produced).	All wastes specified in Appendix G	Maximum storage capacity 305 tonnes, comprising no more than 10 tonnes of hazardous household waste for disposal and no more than 10 tonnes of waste oil. A site layout plan shall be maintained in accordance with condition 1.
R13: Storage of waste consisting of materials intended for submission, on this site to any of the category "R" operations authorised under this column, or elsewhere than on this site, to any of the operations listed in Part IV of Schedule 4 of the 1994 Regulations, (excluding temporary storage, pending collection, on the site where it is produced).		

Specified Waste Management Operations and Exempt Waste Management Operations

- 28.1.2 Where wastes are being brought onto the site for waste management operations which are exempt from licensing under the 1994 Regulations, then the wastes which are subject to the specified waste management operations shall be kept clearly segregated and identified from those wastes which are being kept on the site for the exempt waste management operations.

28.2 Permitted wastes

Permitted categories and types of wastes

- 28.2.1 No wastes other than those, which are categorised below in Table 28.2A and specified in detail in Appendix G to these conditions shall be accepted at the site.

Table 28.2A Permitted quantities of waste

Permitted Waste Categories	Maximum Permitted Quantities for each waste category (subject to maximum permitted total quantity in condition 28.2.2) (tonnes/year)
Inert Household wastes	19,000 tonnes/year
Metal Household wastes	19,000 tonnes/year
Hazardous Household wastes	19,000 tonnes/year
Degradable Household wastes	19,000 tonnes/year

Permitted quantities of wastes

- 28.2.2 The total quantity of waste accepted at the site per year shall not exceed 19,000 tonnes.

Exclusion of waste with specified hazard characteristics

- 28.2.3 Notwithstanding the specification of permitted waste types under condition 28.2.1 above, wastes shall not be accepted at the site which have any of the following characteristics:

Table 28.2B Excluded hazardous wastes with specified hazard codes

Hazard Code	Hazardous Properties
H1	Explosive
H3-A	Highly Flammable
H9	Infectious
H10	Teratogenic
H11	Mutagenic
H12	Substances or preparations which release toxic or very toxic gases in contact with water, air or an acid

29 Site operations

29.1 Waste acceptance and control procedures

Waste acceptance procedures

- 29.1.1 All wastes shall be received, inspected, accepted or rejected, and recorded in accordance with the standards specified in Table 29.1 below.

Waste control procedures

- 29.1.2 All wastes accepted at the site shall be handled, kept and recorded in accordance with the standards specified in Table 29.1 below.

Waste despatch procedures

- 29.1.3 All outgoing wastes shall be inspected, despatched and recorded in accordance with the standards specified in Table 29.1 below.

Table 29.1 Standards for waste acceptance and control procedures

Stage of Waste Handling	Specified standards
a) Waste inspection	Wastes stored at the site shall be regularly checked during the working day to ensure they comply with the permitted waste types detailed in condition 28.2.1 and that they are stored in the appropriate container and location within the site.
b) Waste control procedures: quarantine storage and rejection of wastes	i) Any items of non-permitted waste which are detected after acceptance at the site, shall be placed immediately in a designated quarantine container, and, where these are or appear to be hazardous wastes, the Agency shall be informed immediately; ii) In the quarantine area, wastes shall be kept segregated from other wastes which are or are likely to be incompatible; iii) Quarantined wastes shall be removed from site within 7 days; iv) The maximum quantity of wastes kept in the quarantine storage area shall be 4.6m³ at any one time. v) A record shall be kept in the site diary of all rejected wastes and all wastes kept in quarantine storage.
c) Identification of wastes	i) Areas, bays and containers shall be clearly defined and labelled to identify the wastes stored within them; ii) Containers for hazardous household waste shall be appropriately labelled.
d) Waste despatch procedures	All wastes despatched from the site shall be inspected prior to despatch to confirm their description and composition.
e) Incompatible wastes	Incompatible wastes that are likely, in combination with each other or with other material at the facility, to give rise to pollution of the environment or harm to human health outside the site, shall be clearly identified and kept physically separate in designated areas.

29.2 Storage of hazardous waste with specified hazardous properties or forms

29.2.1 Notwithstanding the specification of permitted waste types under condition 28.2, wastes displaying any of the hazardous properties or forms specified in Table 29.2 shall only be handled and/or stored on the site in accordance with the standards specified in Table 29.2 below or otherwise subsequently agreed with the Agency in writing.

Table 29.2 Standards for handling and/or storage of wastes with specified characteristics

Storage requirement	Specified standards
a) Solid wastes which when handled or stored are likely to generate significant quantities of dusts, fibres or particulates	These wastes only permitted if they are handled and stored either in: i) buildings or containers providing containment of aerial emissions of dusts and particulates; or ii) bays or roofed areas provided with a permanent water supply and water spraying or misting equipment, and with an impermeable pavement and a sealed drainage system; and the water spraying or misting equipment is used at all times when significant quantities of dusts, fibres or particulates are likely to be, or are being generated.
b) Odorous wastes, including wastes which are likely to be odour producing during storage	i) These wastes only permitted if: • stored in sealed containers and in areas provided with impermeable pavement and sealed drainage; or • stored in covered buildings providing containment of aerial emissions; or • stored in bays provided with an impermeable pavement and sealed drainage. ii) These wastes shall not be stored for longer than 48 hours, unless otherwise agreed in writing with the Agency.
c) Solid wastes which are likely to produce polluting or contaminating run-off	i) Inert wastes only permitted if stored in bays with either: • hardstanding and drainage that prevents run-off from the waste into adjacent surface water bodies or storm water drains; or • an impermeable pavement and sealed drainage. ii) Degradable Household wastes only permitted if stored in areas with impermeable pavement and sealed drainage and either: • stored in sealed containers; or • stored in covered shelters or roofed areas; or • stored in bays.
d) Wastes which are in a form which is either sludge or liquid	These wastes only permitted if: • stored in liquid-retaining, covered containers; and • stored in areas provided with impermeable pavement and sealed drainage.
e) Combustible wastes	These wastes only permitted if stored in bays provided with an impermeable pavement and sealed drainage, and with access to fire fighting equipment.
f) Wastes which are likely to attract pests	These wastes shall not be stored for longer than 48 hours, unless otherwise agreed in writing with the Agency.
g) Wastes which are likely to attract scavengers	These waste only permitted if: • stored in closed or secure containers; or • stored in covered buildings providing security against scavengers, or

	• stored in bays provided with netting or fencing providing security against scavengers.
h) Hazardous household waste	Shall only be stored in sealed containers within a secure hazardous waste store. • Lead acid batteries shall be stored in a covered area with an impermeable acid resistant base or acid resistant leak proof container with a close fitting lid.
i) Wastes which include light wastes or other wastes liable to give rise to litter	These wastes only permitted if: • stored in sealed containers and in areas provided with impermeable pavement and sealed drainage; or • stored in covered buildings providing containment of aerial emissions of litter; or • stored in bays provided with litter control netting or fencing.

30 Site records

30.1 **Security and availability of records**

Security of records

- 30.1.1 All records which are required to be made under the conditions of this licence shall be maintained and kept secure from loss, damage or deterioration, and shall be kept in accordance with the requirements specified in Table 30.1 below.

Availability of records

- 30.1.2 All records which are required to be made under the other conditions of this licence shall be made available for inspection at the place where they are kept immediately when required by an authorised officer of the Agency.

Table 30.1 Standards for keeping of site records

Site records	Specified standards
Wastes stored at the site; Wastes rejected; Wastes despatched from the site; Site diaries.	1. All records shall be stored either: a) on paper in a secure cabinet or cupboard; or b) on computer disc with a back up copy. 2. Records of hazardous household waste shall be kept throughout the subsistence of this licence. 3. All other waste records shall be kept for a minimum of two years.

30.2 **Records of waste movements**

Recording of hazardous household waste storage

- 30.2.1 At all times a record shall be maintained of the types and quantities of hazardous household waste stored on site.



LEICESTERSHIRE
COUNTY COUNCIL
PLANNING AND
TRANSPORTATION

T.W. THOMPSON, C.Eng., MICE, FIHT, FRSA,
DIRECTOR OF PLANNING AND TRANSPORTATION

DATE
MY REF:
YOUR REF:
PLEASE ASK FOR:



INTERNAL-1

DIRECT DIALLING



OTHER-2

CONTROL OF POLLUTION ACT 1974
Waste Disposal Licence

Page 1 of 13

BARWELL CIVIC AMENITY SITE
LICENCE NO. 201/1

Condition 1

No deposit shall take place at the site unless at least one month previously a working plan, giving details of the proposed conduct of operations at the site, has been submitted to, and approved by, the Waste Disposal Authority. Any changes to the actual conduct of operations from those detailed in the approved plan, as altered by any previously notified and approved changes, shall not be implemented without the prior written approval of the Waste Disposal Authority. The working plan shall consist of :-

A) The written working plan shall include details of the following :-

- 1) Site access road and site surface construction, including details of vehicular circulation routes.
- 2) Provision and position of any bays for containers or waste.
- 3) Provision for storage of skips and containers.
- 4) Buildings on, or associated with, the site, including any septic or drainage tanks and other services to the building.
- 5) Construction and position of any fences and gates.
- 6) Hours of working and provision of service over bank holiday period.
- 7) Machinery type and storage facilities where appropriate.

- 8) Manning levels.
- 9) Security precautions out of hours.
- 10) Capacity of site and arrangements for waste when site is full.
- 11) Arrangements for sweeping the site and site roads to maintain them in a clean condition.
- 12) Methods to control litter.

B) A plan or series of plans as follows :-

- 1) A site location plan.
On a suitable scale to identify the site in comparison with the Ordnance Survey Map of the area.
- 2) A site operational and engineering plan.
To show the site after its preparation, including method of working and details of any engineered features.

Condition 2

This Licence shall apply to the site shown on the Plan reference number 201/1 submitted with the Waste Disposal Site Licence Application.



Originating from household waste only, as defined in Section 1(i) of the Refuse and Disposal (Amenity) Act 1978. No special wastes other than batteries and no clinical or trade waste are to be accepted on site.

Condition 4

Batteries are to be stored upright within a covered container.

Condition 5



Condition 6

Full skips should be transported to and emptied at a suitably licenced waste disposal facility within 3 days of filling and in any case all waste should be removed within 7 days of deposit.

Condition 7

No deposit shall take place unless a road has first been provided within the site. This shall be constructed to a specification and at locations as stated in the working plan which forms part of this Licence.

Condition 8

No deposit shall take place until a site control office has been provided on the site, affording toilet, washing and eating facilities and containing adequate first aid equipment

Condition 9

All oil containers are to be kept within the bunded area or, when empty, within the household refuse skip. No containers are to be kept outside the bunded area at any time.

Condition 10

Site drainage around the oil store should be drained through an oil/water interceptor prior to discharge to the surface water system. This should be implemented within two years of the date of issue of this licence.

Condition 11

No deposit shall take place until a site identification board of durable material and finish and of a minimum 1m² surface and has been displayed at the site entrance, showing the hours when the site is open and giving the name of the site, the name, address and telephone number of the operator (and his local agent) and of the Waste Disposal Authority responsible for issuing the site licence and a telephone number to be used in case of an emergency.

Condition 12

Signs shall be erected on site to indicate traffic direction and to inform the public of the designation of containers.

Condition 13

- a) Any tanks used for the storage of liquid within the site shall be surrounded by a bund capable of impounding the capacity of the largest tank plus 10%.

- b) Any tank shall be of a type and construction suitable for the liquid it contains and shall be labelled to show its contents.
- c) The wall and floor of the bund should not contain any drain value, the capacity should be maintained by way of a bailer or pump. All filling points, vents and sight glasses must be located within the bund.
- d) Any bunded area shall be maintained and shall be kept dry.
- e) The surface of any bunded area, together with the bunds themselves, shall be constructed of a material impermeable to any liquids stored in that area.

Condition 14

No deposit shall take place until water courses on the site have been diverted, culverted or otherwise protected and as laid down in the working plan which forms a part of this Licence.

Condition 15

No deposit shall take place until suitable facilities have been provided for storing and maintaining equipment used on the site.

Condition 16

Measures shall be taken, as specified in the working plan which forms part of this Licence, to contain paper and other windblown materials within the site. Any windblown material carried off the site shall be collected and disposed of immediately.

Condition 17

Fencing shall be provided and maintained to impede unauthorised access and prevent accidental access to the site. A gate or similar barrier shall be erected at the site entrance and shall be kept locked in the closed position at all times when the site is closed or unattended.

Condition 18

No working shall take place on the site during the hours of darkness unless lighting is provided, maintained and used.

Condition 19

Hours of working shall be:-

* April - October	0800 hrs - 2000 hrs
November - March	0800 hrs - 1800 hrs
Saturday - Saturday inclusive	

There is to be no working on Christmas Day.

Condition 20

The site shall be manned while it is being operated and while it is operational it shall be supervised by a person competent and qualified to ensure compliance with this licence and its conditions.

Condition 21

No waste material shall be burnt within the boundaries of the site and a fire at the site shall be regarded as an emergency and immediate action shall be taken to extinguish it. All outbreaks of fire shall be notified forthwith to the Waste Disposal Authority, on Leicester 323232 Extension 7241.

Condition 22

Measures shall be taken to deal effectively with any vermin and insects on the site.

Condition 23

The terms of the site licence shall be made known to any person who is given responsibility for the management, supervision or control of the site and a copy of the licence conditions shall be displayed at the site control office.

Condition 24

Not less than 14 days notice in writing shall be given to the Waste Disposal Authority of the date on which operations are to commence or recommence in the event of a temporary cessation for a period in excess of three months.

Condition 25

Any temporary cessation of operations for a period in excess of three months shall be notified to the Waste Disposal Authority.

Condition 26

Waste of a certain type shall be deposited in a skip specifically designated for that type of waste where provided.

Condition 27

Glass should be broken down as detailed in the working plan which forms part of this licence.

NOTICE TO THE HOLDER OF THE LICENCE


1. Attention is drawn to the Licence holders statutory obligations under other legislation and in particular to the Health and Safety at Work etc. Act 1974, the Radio-active Substance Act 1960, and also Planning, Water Protection and Environmental Health legislation.
2. Injuries, diseases or dangerous occurrences resulting from operations at the site must be reported by the Licence holder to the appropriate enforcing authority in accordance with the Reporting of Injuries Diseases and Dangerous Occurrences Regulations 1985 (RIDDOR).

Where the H.S.E. is the enforcing authority reports should be sent to the Health and Safety Executive, Belgrave House, 1 Greyfriars, Northampton, NN1 2BS. Where the Local Authority is the enforcing authority reports should be sent to the Chief Environmental Health Officer.

3. On completion of the site the Waste Disposal Authority, Licensing Section, shall be contacted in order to carry out an inspection prior to the Licence being terminated.

CONDITIONS CONTINUED

PAGE 7 OF 13








This category excludes all materials or all wastes contaminated with other materials from Categories B to F



This category excludes all materials or all wastes contaminated with other materials from Categories C to F








CONDITIONS CONTINUED

PAGE 13 OF 13



29th March, 1993

7298F

PT.299



LEICESTERSHIRE
COUNTY COUNCIL

BARWELL CIVIC AMENITY SITE
LOCATION PLAN
SCALE 1:2500

